### INTEGRATED CIRCUITS

# DATA SHEET

### **CBTD16211**

24-bit level shifting bus exchange switch with 12-bit output enables

Product data 2001 Jun 13





## 24-bit level shifting bus exchange switch with 12-bit output enables

**CBTD16211** 

#### **FEATURES**

- $5\Omega$  switch connection between two ports
- TTL compatible control input levels
- Designed to be used in level shifting applications
- Package options include shrink small outline (SSOP) and thin shrink small outline (TSSOP)
- ESD protection exceeds 1000 V CDM per JESD22-C101
- Latch-up testing is done to JESDEC Standard JESD78 which exceeds 100 mA

#### **DESCRIPTION**

The CBTD16211 provides 24 bits of high-speed TTL-compatible bus switching. The low on-state resistance of the switch allows connections to be made with minimal propagation delay.

A diode to  $V_{CC}$  is integrated in the circuit to allow for level shifting between 5 V inputs and 3.3 V outputs.

The device is organized as a dual 12-bit bus switch with separate output-enable  $(\overline{OE})$  inputs. It can be used as two 10-bit bus switches or as one 20-bit bus switch. When  $\overline{OE}$  is low, the associated 10-bit bus switch is on, and port A is connected to port B. When  $\overline{OE}$  is high, the switch is open, and a high-impedance state exists between the ports.

The CBTD16211 is characterized for operation from -40 to +85 °C.

#### **QUICK REFERENCE DATA**

SYMBOL	PARAMETER	CONDITIONS T <sub>amb</sub> = 25 °C; GND = 0 V	TYPICAL	UNIT
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay An to Yn	$C_L = 50 \text{ pF}; V_{CC} = 5 \text{ V}$	0.25	ns
C <sub>IN</sub>	Input capacitance	V <sub>I</sub> = 0 V or V <sub>CC</sub>	4.3	pF
C <sub>OUT</sub>	Output capacitance	Outputs disabled; V <sub>O</sub> = 0 V or V <sub>CC</sub>	6.9	pF
I <sub>CC</sub>	Total supply current	Outputs disabled; V <sub>CC</sub> = 5.5 V	3.0	μΑ

#### ORDERING INFORMATION

PACKAGES	TEMPERATURE RANGE	ORDER CODE	DWG NUMBER
56-Pin Plastic SSOP Type III	−40 to +85 °C	CBTD16211DL	SOT371-1
56-Pin Plastic TSSOP Type II	−40 to +85 °C	CBTD16211DGG	SOT364-1


#### **FUNCTION TABLE**

INP	JTS	OUTPUTS				
1 <del>OE</del>	2 <del>0E</del>	1A, 1B	2A, 2B			
L	L	1A = 1B	2A = 2B			
L	Н	1A = 1B	Z			
Н	L	Z	2A = 2B			
н	Н	Z	Z			

H = High voltage levelL = Low voltage level

Z = High impedance "off" state


#### **LOGIC SYMBOL**



## 24-bit level shifting bus exchange switch with 12-bit output enables

### CBTD16211

#### **PIN CONFIGURATION**



### **PIN DESCRIPTION**

PIN NUMBER	SYMBOL	NAME AND FUNCTION
1	NC	No internal connection
56, 55	10E, 20E	Output enables
2, 3, 4, 5, 6, 7, 9, 10, 11, 12, 13, 14	1A1-1A12	Inputs
54, 53, 52, 51, 50, 48, 47, 46, 45, 44, 43, 42	1B1-1B12	Outputs
15, 16, 18, 20, 21, 22, 23, 24, 25, 26, 27, 28	2A1-2A12	Inputs
41, 40, 39, 37, 36, 35, 34, 33, 32, 31, 30, 29	2B1-2B12	Outputs
8, 19, 38, 49	GND	Ground (0 V)
17	V <sub>CC</sub>	Positive supply voltage

## 24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16211

### ABSOLUTE MAXIMUM RATINGS1, 2

SYMBOL	PARAMETER	CONDITIONS	RATING	UNIT
V <sub>CC</sub>	DC supply voltage		-0.5 to +7.0	V
I <sub>IK</sub>	DC input diode current	V <sub>I</sub> < 0	-50	mA
VI	DC input voltage <sup>3</sup>		-0.5 to +7.0	V
V <sub>OUT</sub>	DC output voltage <sup>3</sup>	output in Off or High state	−0.5 to +5.5	V
I <sub>OUT</sub>	DC output current	output in Low state	128	mA
T <sub>stg</sub>	Storage temperature range		-65 to +150	°C

#### NOTES:

- Stresses beyond those listed may cause permanent damage to the device. These are stress ratings only and functional operation of the
  device at these or any other conditions beyond those indicated under "recommended operating conditions" is not implied. Exposure to
  absolute-maximum-rated conditions for extended periods may affect device reliability.
- 2. The performance capability of a high-performance integrated circuit in conjunction with its thermal environment can create junction temperatures which are detrimental to reliability. The maximum junction temperature of this integrated circuit should not exceed 150 °C.
- 3. The input and output voltage ratings may be exceeded if the input and output current ratings are observed.

#### RECOMMENDED OPERATING CONDITIONS

SYMBOL	PARAMETER	LIM	UNIT	
STWIBOL	FARAMETER	Min	Max	UNIT
V <sub>CC</sub>	DC supply voltage	4.5	5.5	V
V <sub>IH</sub>	High-level input voltage	2.0	_	V
V <sub>IL</sub>	Low-level Input voltage	_	0.8	V
T <sub>amb</sub>	Operating free-air temperature range	-40	+85	°C

#### DC ELECTRICAL CHARACTERISTICS

				LIMITS			
SYMBOL	PARAMETER	TEST CONDITIONS	T <sub>amb</sub>	UNIT			
			Min	Min Typ <sup>1</sup> N		ıx	
$V_{IK}$	Input clamp voltage	V <sub>CC</sub> = 4.5 V; I <sub>I</sub> = -18 mA	T -	_	-1.2	V	
V <sub>OH</sub>	Output high pass voltage	See Figure 1	-	_		V	
	lament lamba an arrange	V <sub>CC</sub> = 0 V; V <sub>I</sub> = 5.5 V	_	_	10		
l <sub>l</sub>	Input leakage current	V <sub>CC</sub> = 5.5 V; V <sub>I</sub> = GND or 5.5 V	_	_	±1	μΑ	
I <sub>CC</sub>	Quiescent supply current	$V_{CC} = 5.5 \text{ V}$ ; $I_O = 0$ , $V_I = V_{CC}$ or GND; $1\overline{OE} = 2\overline{OE} = GND$	_	_	1.5	mA	
$\Delta I_{CC}$	Additional supply current per input pin <sup>2</sup>	$V_{CC}$ = 5.5 V, one input at 3.4 V, other inputs at $V_{CC}$ or GND	_	_	2.5	mA	
CI	Control pins	V <sub>I</sub> = 3 V or 0	_	4.5	_	pF	
C <sub>I(OFF)</sub>	Port OFF capacitance	$V_O = 3 \text{ V or } 0, \overline{OE} = V_{CC}$	_	8	_	pF	
		V <sub>CC</sub> = 4.5 V; V <sub>1</sub> = 0 V; I <sub>I</sub> = 64 mA	<u> </u>	5	7		
$r_{on}^3$		V <sub>CC</sub> = 4.5 V; V <sub>1</sub> = 0 V; I <sub>I</sub> = 30 mA	T -	5	7	Ω	
		$V_{CC} = 4.5 \text{ V}; V_1 = 2.4 \text{ V}; I_1 = -15 \text{ mA}$	_	35	50	1	

#### NOTES:

- 1. All typical values are at  $V_{CC}$  = 5 V,  $T_{amb}$  = 25 °C.
- 2. This is the increase in supply current for each input that is at the specified TTL voltage level rather than V<sub>CC</sub> or GND.
- Measured by the voltage drop between the A and the B terminals at the indicated current through the switch. On-state resistance is determined by the lowest voltage of the two (A or B) terminals.

2001 Jun 13

## 24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16211

#### **AC CHARACTERISTICS**

 $GND = 0 V; t_{R;} C_{L} = 50 pF$ 

SYMBOL	PARAMETER	FROM (INPUT)	TO (OUTPUT)	V <sub>CC</sub> = 5.0	UNIT	
				Min	Max	
t <sub>pd</sub>	Propagation delay <sup>1</sup>	A or B	B or A	_	0.25	ns
t <sub>en</sub>	Output enable time to High and Low level	ŌĒ	A or B	1.5	8.5	ns
t <sub>dis</sub>	Output disable time from High and Low level	ŌĒ	A or B	1.5	7	ns


#### NOTE:

<sup>1.</sup> This parameter is warranted but not production tested. The propagation delay is based on the RC time constant of the typical on-state resistance of the switch and a load capacitance of 50 pF, when driven by an ideal voltage source (zero output impedance).


## 24-bit level shifting bus exchange switch with 12-bit output enables

### CBTD16211

#### **AC WAVEFORMS**




Waveform 1. Input (An) to Output (Yn) Propagation Delays



Waveform 2. 3-State Output Enable and Disable Times

#### **TEST CIRCUIT AND WAVEFORMS**



#### **TYPICAL CHARACTERISTICS**





Figure 1.  $V_{OH}$  values  $(V_{in} = V_{CC})$ 

### SSOP56: plastic shrink small outline package; 56 leads; body width 7.5 mm

SOT371-1



#### **DIMENSIONS (mm are the original dimensions)**

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	b <sub>p</sub>	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	2.8	0.4 0.2	2.35 2.20	0.25	0.3 0.2	0.22 0.13	18.55 18.30	7.6 7.4	0.635	10.4 10.1	1.4	1.0 0.6	1.2 1.0	0.25	0.18	0.1	0.85 0.40	8° 0°

#### Note

1. Plastic or metal protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ISSUE DATE		
VERSION	IEC	JEDEC	EIAJ		PROJECTION	ISSUE DATE
SOT371-1		MO-118				<del>95-02-04</del> 99-12-27


2001 Jun 13

## 24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16211

### TSSOP56: plastic thin shrink small outline package; 56 leads; body width 6.1 mm

SOT364-1



#### DIMENSIONS (mm are the original dimensions).

UNIT	A max.	Α1	A <sub>2</sub>	A <sub>3</sub>	bp	С	D <sup>(1)</sup>	E <sup>(2)</sup>	е	HE	L	Lp	Q	v	w	у	Z	θ
mm	1.2	0.15 0.05	1.05 0.85	0.25	0.28 0.17	0.2 0.1	14.1 13.9	6.2 6.0	0.5	8.3 7.9	1.0	0.8 0.4	0.50 0.35	0.25	0.08	0.1	0.5 0.1	8° 0°

#### Notes

- 1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
- 2. Plastic interlead protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ISSUE DATE		
VERSION	IEC	JEDEC	EIAJ		PROJECTION	ISSUE DATE
SOT364-1		MO-153				<del>-95-02-10-</del> 99-12-27

## 24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16211

#### Data sheet status

Data sheet status <sup>[1]</sup>	Product status <sup>[2]</sup>	Definitions
Objective data	Development	This data sheet contains data from the objective specification for product development.  Philips Semiconductors reserves the right to change the specification in any manner without notice.
Preliminary data	Qualification	This data sheet contains data from the preliminary specification. Supplementary data will be published at a later date. Philips Semiconductors reserves the right to change the specification without notice, in order to improve the design and supply the best possible product.
Product data	Production	This data sheet contains data from the product specification. Philips Semiconductors reserves the right to make changes at any time in order to improve the design, manufacturing and supply. Changes will be communicated according to the Customer Product/Process Change Notification (CPCN) procedure SNW-SQ-650A.

[1] Please consult the most recently issued datasheet before initiating or completing a design.

[2] The product status of the device(s) described in this data sheet may have changed since this data sheet was published. The latest information is available on the Internet at URL http://www.semiconductors.philips.com.

#### **Definitions**

**Short-form specification** — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

**Limiting values definition** — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

**Application information** — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

#### **Disclaimers**

**Life support** — These products are not designed for use in life support appliances, devices or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

Right to make changes — Philips Semiconductors reserves the right to make changes, without notice, in the products, including circuits, standard cells, and/or software, described or contained herein in order to improve design and/or performance. Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

Philips Semiconductors 811 East Arques Avenue P.O. Box 3409 Sunnyvale, California 94088–3409 Telephone 800-234-7381 © Copyright Philips Electronics North America Corporation 2001 All rights reserved. Printed in U.S.A.

Date of release: 06-01

Document order number: 9793 750 08482

Let's make things better.

Philips Semiconductors



